



**NOTE:**  
 TRAFFIC TO BE KEPT OFF CONCRETE COLLAR FOR A MINIMUM OF 48 HOURS.

CONSTRUCTION ITEMS / MATERIALS LIST		
NO.	SIZE AND DESCRIPTION	MANUFACTURER
①	GATE VALVE, RESILIENT WEDGE	CLOW, MUELLER, OR EQUAL
②	VALVE BOX FRAME & COVER, C.I.	BROOKS 4TT FOR TRAFFIC USE OR EQUAL
③	P.V.C. PIPE, 8", SCHEDULE 40	_____
④	CONCRETE COLLAR	CONCRETE CLASS (560-C-3250)

**NOTES:**

- ALL BURIED BOLTS SHALL BE COATED WITH 2 COATS OF MASTIC SUCH AS "3M" BRAND EC 244 OR EQUAL.
- ALL BURIED IRON SHALL BE WRAPPED WITH 1 LAYER OF 10 MIL POLYETHYLENE SHEETING TAPED IN PLACE.

ⓐ PAVEMENT BASE MATERIAL OR COMPACTED SOIL.

APPROVED: \_\_\_\_\_ DATE: 3/8/2016

*Naimi Bawa*

CITY OF SANTA ANA  
 PUBLIC WORKS AGENCY



DATE		REVISION
5/12/00	C.E.B.	CREATED RESIDENTIAL STD.
9/28/01	A.F.	UPDATED
6/4/13	J.A.	ADDED REBAR
3/1/16	R.R.	REMOVED RAPID SET

GATE VALVE INSTALLATION

STD. PLAN NUMBER  
 1410